

S. Pinckney Street Assessment District - 2023 (Street Resurfacing & Storm Sewer)

Public Information Meeting
City of Madison Engineering Division
September 22, 2022

Thank you for attending. We will begin shortly...




Meeting Technical Housekeeping

- This meeting will be <u>recorded</u> and posted to the project page.
- All attendees should be <u>muted</u> to keep background noise to a minimum.
- Use the <u>"chat"</u> button for technical issues with meeting to troubleshoot with staff to assist.
- Use the <u>"Q and A"</u> button to type questions about presentation.
 Questions will be answered live after the presentation.
- Inappropriate questions may be dismissed.
- Use the "raise your hand" button to verbally ask your question. You will be prompted to unmute when it is your turn.

This meeting is being recorded. It is a public record subject to disclosure.


By continuing to be in the meeting, you are consenting to being recorded and consenting to this record being released to public record requestors.












Raise your hand to be unmuted For comments or ask additional questions.








Use chat if you have technical issues or a question for the panelists








Use Q/A if you have questions. We will answer after the presentation





To leave the meeting click here




Presentation Overview

- ➤ Project Location
- **➤** Existing Conditions
- ➤ Proposed Design
- ➤ Forestry Information
- ➤ Construction & Access
- ➤ Assessment Policy & Costs
- ➤ Project Schedule
- ➤ Contact Information & Resources



Project Location



Project Limits

S. Pinckney St: E. Doty St to E. Wilson St




Existing Conditions

Item	Existing Condition
Last Surfaced	Resurfaced 1982
Pavement Surface Evaluation & Rating	Asphalt Surface. Longitudinal and transverse cracking. Rating 5
Curb Rating	10 - 216 S. PINCKNEY ST SIDE, REMOVED 2018 – 231 S. PINCKNEY ST SIDE
Width	48 feet face to face
Surface	Asphalt
Sidewalk	On both sides
Sanitary	N/A
Water	N/A
Storm	15 inch RCP installed 2018

Proposed Design

- ➤ Street Construction
 - Place asphalt pavement upper layer (lower layer installed 2018)
 - Install concrete curb and gutter along 231 S. Pinckney St (valet pullout area adjacent to hotel development)
 - Install street median island with pedestrian curb ramps
 - Install bike lane pavement markings
- ➤ City Utility Reconstruction
 - Sanitary N/A
 - Storm Replace storm sewer, replace storm inlets, and install private storm connections as needed. Storm sewer pipe will be upsized to 21 inch RCP.
 - Water N/A
 - Lighting/Signals N/A
- ➤ Additional Coordination
 - City Forestry Two tree plantings within new street median island
 - Madison Gas and Electric Private utility relocations as needed
 - Median island art installation







Future Street Construction (2024)



- ➤ E. Doty St (Martin Luther King Jr. Blvd to King St)
- ➤ E. Wilson St (Martin Luther King Jr. Blvd to King St)
- ➤ E. Wilson St will be constructed per approved corridor study:

https://www.cityofmadison.com/transportation/st udies/wilson-street-corridor-study



Forestry Information

- ➤ City Engineering will review the project with City Forestry and a Forestry representative will work with the contractor and inspector during construction.
- ➤ City Forestry will perform tree pruning prior to construction in order to provide the required clearance above the street.
- After the project is complete, City Forestry will evaluate the new terraces within City right-of-way for new and replacement planting sites
- The minimum terrace width for planting is 5 feet
- ➤ No anticipated tree removals at this time
- Two tree plantings anticipated within street median island (2" Hackberry)
- ➤ Median island trees will be maintained by the City



Construction & Access

- ➤ Street open to local traffic (residents)
- ➤ No street parking allowed 7 AM to 7 PM
- ➤ Overnight parking will be available to local traffic
- ➤ Parking restrictions on adjacent streets may be temporarily lifted to allow for additional parking
- ➤ Contractor responsible for daily street sweeping and dust mitigation



Construction & Access – Water Shut-Offs

- ➤ No planned water shut-offs
- Emergency shut-offs may occur if the existing main is damaged during construction.

Assessment Policy & Costs

- ➤ Property owners will receive an estimate of their assessment prior to construction
- In most cases, the final assessment is less than or equal to the estimate
- Final assessments will be mailed in the summer of 2024 following completion of the project
- Final assessments will be calculated based on actual bid prices and measured quantities
- Final assessments are payable as a lump sum or over 8 years with 2% interest
- Property owners adjacent to the project will be assessed for all assessable items of work
- ➤ Corner lots (single or two family residential) receive 50% assessments for sidewalk and curb replacements



Assessment Policy & Costs

ltem	City Share	Owner Share	
Curb, Sidewalk, Drive Aprons	50%	50%	
Sanitary Laterals	75%	25%	
Private Storm Connection	0%	100%	
Asphalt Pavement	100%	0%	
Sanitary & Storm Mains	100%	0%	
Water Main	100%	0%	
Sidewalk Ramps	100%	0%	
Terrace Steps	0%	100%	
Intersection Improvements	100%	0%	



Project Schedule

- ➤ September 30, 2022: Mail Estimated Assessments & Public Hearing Notice
- ➤ October 12, 2022: BPW Approval Public Hearing
- ➤ October 25, 2022: Common Council Approval Hearing
- November 17, 2022: Advertise for Bids
- ➤ April 2023: Anticipated Start of Construction
- ➤ June 2023: Anticipated End of Construction



Contact Information & Resources

Project Manager	Reid Stiteley	608-266-4093	rstiteley@cityofmadison.com
Storm Engineer	Kyle Frank	608-266-4098	kfrank@cityofmadison.com
Traffic Engineer	Alexandra Heinritz	608-267-1102	aheinritz@cityofmadison.com
Forestry Specialist	Brad Hofmann	608-267-4908	bhofmann@cityofmadison.com
Public Information Officer	Hannah Mohelnitzky	608-669-3560	hmohelnitzky@cityofmadison.com

- Project Website: https://www.cityofmadison.com/engineering/projects/s-pinckney-street-resurfacing
- Sign-up for project email updates on the website
 - Updates on closures & work progress will be posted to the project website
 - Recording for this meeting will be posted on project webpage



Facebook: City of Madison Engineering



Twitter: @MadisonEngr



Everyday Engineering Podcast: iTunes, GooglePlay

